

BRUHAT BANGALORE MAHANAGARA PALIKE

DASARAHALLI ZONE

Name of Work: Construction and Repairs to Culverts in Dasarahalli Ward No 15

			Est. Cost Rs				25.00	Lakhs	
Sl	Description of Item	Unit	No	L	B	D	Qty	Rate	Amount
1	KSRRB 300 - Excavation for road, drains and similar works - KSRRB 300 1. Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter 3 (P.142/I.19.1 PW, P & IWTD -SR 2016-17)								
		Cum	23	6.00	2.00	1.00	276.00		
	Basic Rate	82.00					276.00	86.92	23990.00
	Add Area Weightage 6%	4.92							
	Total	86.92							
2	KSRRB M2100-10. Plain cement concrete M-10 with OPC cement at 220kg with crushed 40mm down size graded granite metal course aggregate @0.84 CUM and fine agreegate @ 0.6 CM in Foundation mechanically mixed placed in foundation and compacted by vibration including curing for 14 days complete as per specifications. MORTH Specification No. 2100. Page No. 218/ Item No. 27.18/ PWD SR 2016-17								
		Cum	23	6.00	2.00	0.15	41.40		
	Basic Rate	5634.00					41.40	5972.04	247242.00
	Add Area Weightage 6%	338.04							
	Total	5972.04							
3	KSRRB 4-6.3: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness above 200 mm including cost of all materials, labour complete as per specifications.(Page No: 15, itno: 4.30) 2016-17								
	Sqm		23	4	6	0.85	469.20		
			23	1	6.00	2.00	12.00		
	Basic Rate	384.00					481.20	407.04	195868.00
	Add Area Weightage 6%	23.04							
	Total	407.04							
4	KSRRB M2200-5.9 Design Mix M20 with OPC cement @ 320kgs with 20mm & down size graded granite metal course agreegate @ 0.69 CM an Fine agregated 0.46 cm with super plaster @ 3ltrs confirming to IS 9103-1999 Reaffirmed -2008 i.) Upto 5m height Page No. 223/ Item No. 28.7.9/ PWD SR 2016-17								

Sl	Description of Item	Unit	No	L	B	D	Qty	Rate	Amount
		23	2	6.00	0.30	0.85	70.38		
		23	1	6.00	2.00	0.35	96.60		
	Basic Rate	6571.00					166.98	6965.26	1163059.00
	Add Area Weightage 6%	394.26							
	Total	6965.26							
5	KSRB M-2200- TMT/MS bar Reinforcement KSRRB M2200-6 Supplying, fitting and placing TMT bar reinforcement in Sub-structure complete as per drawing and technical specifications complete as per specifications. MORTH specification No. 1600 & 2200. Page No. 225/ Item No. 28.8/ PWD SR 2016-17 TMT Bars FE 550								
	For Bottom & Sides	Tonnes	167		86.00		14360.28		
							14360.28		
	Basic Rate	55484.00				Say	14.36	58813.04	844572.00
	Add Area Weightage 6%	3329.04							844572.00
	TOTAL	58813.04							
6	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Page No. 150 Item No. 17.1 PWD SR 2016-17								
		Cum				Qty Vide Item No. 1	276.00	80.80	22301.60
								85.65	23639.00
	Loading and Unloading	68.00							
	Lead 4 KMs	2x1.28x4	12.80						
			80.80						
	Add Area Weightage 6%	4.85							
	Total	85.65							
7	Quality control Test Charges 1%								
									2985.00
8	Miscellaneous and Unforeseen Charges								
									1630.00
	Total								2500000.00

(Rupees.Twenty Five Lakhs Only)

CERTIFICATE:-

- 1 The Work spot has been inspected and the work is found to be necessary
- 2 The Estimate is prepared as per the PW,P & IWTD -SR-2016-17
- 3 The Provision made in estimate are adequate and essential.
- 4 This area comes under BBMP limits.

Assistant Engineer
Ward-15

Assistant Executive Engineer
T. Dasarahalli Sub-Division
B.B.M.P.

Executive Engineer
Dasarahalli Division
B.B.M.P. Bangalore

ನಂ. CE/AS/66/16-17 ದಿನಾಂಕ : 09/01/2017
ರೂ. 25.00 Lakh /- Rupees Twenty five Lakh only /-
ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಅಡಕತೆಪಟ್ಟ ಮುಖ್ಯಸ್ಥರು
ದಾಸರಾಹಳ್ಳಿ

ನಂ. CE/RE/114/16-17 ದಿನಾಂಕ : 27/01/2017
ರೂ. 25.00 Lakh Rupees only /-
ಈ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಅಡಕತೆಪಟ್ಟ ಮುಖ್ಯಸ್ಥರು
ತಾಂತ್ರಿಕ ಸಹಾಯಕರು ಬಿ.ಬಿ.ಎಂ.ಪಿ.
ದಾಸರಾಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು